


Libby Flood Control Operation


VARQ in 2007
TMT Meeting January 31, 2007

Cindy Henriksen
US Army Corps of Engineers




Libby Dam Operations

- *2006 Documentation*
 - *Final Upper Columbia EIS*
 - *Public Meeting briefings*
 - *After Action Report*
- *January Determination and Finding*
- *What to Expect in 2007*
 - *VARQ Flood Control*
 - *Fish (Sturgeon Operation)*
 - *Summer Salmon Operation*
- *Reduced Flexibility in 2007*



2006 Documentation

- *Final Upper Columbia EIS*
http://www.nws.usace.army.mil/Template/Display/More_Hot_Topics.cfm?recno=56
- *Public Meeting at Bonners Ferry September 6, 2006*
<http://www.nws.usace.army.mil/PublicMenu/Menu.cfm?sitename=PUBLICAFFAIRS&pagename=SpringEvent2006>
- *Public Meeting at Bonners Ferry November 6, 2006*
- *After Action Report posted on the web page above*



January Determination and Finding




- *Signed by General Martin January 5, 2007*
http://www.nws.usace.army.mil/PublicMenu/documents/PUBLICAFFAIRS/Libby_Decision_Document_07.pdf
- *This is a one year decision*
- *Operate in accordance with the VARQ procedures such that there will be no reduction in flood storage capability*




What to Expect in 2007

- *VARQ Flood Control*
- *Adhere to the VARQ procedures*
- *Draft through March using VARQ SRD*
- *Begin VARQ refill outflow at Libby 10 days prior to the ICF*
- *VARQ outflow will be calculated each week*
- *VARQ outflow will not be reduced except for one or two days to protect human life and safety*
- *Manage to avoid exceeding a stage of elevation 1764 feet at Bonners Ferry to the extent practicable*




What to Expect in 2007

- *Sturgeon Operation*
- *Meet the volume recommended for the sturgeon tier*
- *Current WSF is 6.995 MAF (110%)*
- *The corresponding tiered volume is 1.169 MAF (approximately 28 days at full powerhouse)*
- *Discussion will be initiated to determine the 2007 sturgeon flow operation*



Reduced Flexibility in 2007

- *VARQ refill outflow will begin on schedule ten days prior to the Initial Controlled Flow (ICF) at The Dalles*
 - *If the ICF date is computed to be later, VARQ outflow may be reduced during the next calculation*
 - *If the ICF date is earlier, VARQ outflow may be greater and spill may be needed to meet the flow*
- *Start of Sturgeon flow will be coordinated through the TMT*



Reduced Flexibility in 2007

- *Refill in 2007 may not be as likely as it was in past years*
- *The UCEIS was based on refill by July 31*
- *The refill probability in the UCEIS included the double peak operation nearly half the years modeled*
- *To reduce the double peak reduces the refill probability further than that modeled*

*VARQ operations can have fish flows overlaid –
Impact to refill was characterized in UCEIS*

*(LVI is Libby Operation with VARQ flood control and a
sturgeon operation at full powerhouse outflow. LV2 is
Standard Flood Control with full powerhouse plus 10,000 cfs)*

Alternative	Percent of years with peak Libby Reservoir elevation \geq 2458 feet (1 ft from full pool elevation before July 31)	Percent of years with peak Libby Reservoir Elevation \geq 2454 feet (5 ft from full pool elevation by July 31)
LS1	6	12
LV1	12	31
LS2	6	10
LV2	10	31




Reduced Flexibility in 2007

- *May be increased chance of double peak*
- *Potential for spill to meet required VARQ outflow*
- *Potential spill to meet VARQ outflow if a unit or transmission outage occurs*

ESP (1/23/07) INFLOWS USED STARTING 1/29/07

APR-AUG VOLUME=6.890 MAF

Libby Operations Based on Jan Final Forecast 6.955 MAF



ESP (1/23/07) INFLOWS USED STARTING 1/29/07

APR-AUG VOLUME=6.589 MAF

Libby Operations Based on Feb Final Forecast 6.5 MAF

