

**ICF and GCL Storage Corrections, kaf
Forecast of System Flood Control for**

	WY 2008				
Forecast Date (1)	1-JAN	1-FEB	1-MAR	1-APR	1-MAY
MCDB					
May-Jul; Inflow minus Outflow, kaf	7194	7008	6976	6805	6980
Projected Space Available, 30-Apr, kaf	7692	9238	8697	9779	10025
Required Flood Control Draft, kaf	4080	4080	4080	4080	4080
Storage Adjustment to TDA, kaf	7194	7008	6976	6805	6980
LIB					
May-Jul; Inflow minus Outflow, kaf	4485	4663	4699	4565	4594
Projected Space Available, 30-Apr, kaf	2129	2496	2389	2308	2519
Required Flood Control Draft, kaf	2157	2520	2587	2323	1848
Storage Adjustment to TDA, kaf	2129	2496	2389	2308	2519
DCDB					
May-Jul; Inflow minus Outflow, kaf	1672	1596	1590	1569	1553
Projected Space Available, 30-Apr, kaf	1364	1309	1270	1399	1392
Required Flood Control Draft, kaf	1270	1270	1270	1270	1255
Storage Adjustment to TDA, kaf	1364	1309	1270	1399	1392
HGH					
May-Jul; Inflow minus Outflow, kaf	1549	1566	1581	1616	1834
Projected Space Available, 30-Apr, kaf	743	807	870	1077	1295
Required Flood Control Draft, kaf	743	769	793	845	1198
Storage Adjustment to TDA, kaf	743	807	870	1077	1295
DWR					
May-Jul; Inflow minus Outflow, kaf	1768	1783	1836	1984	2443
Projected Space Available, 30-Apr, kaf	1328	1343	1396	1584	1725
Required Flood Control Draft, kaf	1328	1343	1396	1544	2003
Storage Adjustment to TDA, kaf	1328	1343	1396	1584	1725
ARDB					
Projected Space Available, 30-Apr, kaf	4907	4649	3600	3600	3591
Required Flood Control Draft, kaf	3600	3600	3600	3600	3600
Storage Adjustment to TDA, kaf	3600	3600	3600	3600	3591
BRN					
Projected Space Available, 30-Apr, kaf	325	469	520	508	578
Required Flood Control Draft, kaf	325	469	520	508	409
Storage Adjustment to TDA, kaf	325	469	520	508	578
FIXED STORAGE CORRECTION, KAF					
KERM	500	500	500	500	500
NOX	0	0	0	0	0
ALF	500	500	500	500	500
JDA	158	158	158	158	158
TOTAL CORRECTION UPSTREAM OF GCL					
	17841	18190	18179	18439	19238
TDA APR-AUG FORECAST, kaf	88200	91800	94300	94700	90900
ADJUSTED TDA APR-AUG FORECAST, kaf	70359	73610	76121	76261	71662
GCL					
Projected Space Available, 30-Apr, kaf	3382	3828	4131	4154	4088
Required Flood Control Draft, kaf	3382	3828	4137	4154	3583
Storage Adjustment to TDA, kaf	3382	3828	4131	4154	4088
IRRIGATION ADJUSTMENT, kaf	1671	1671	1671	1671	1671
TOTAL CORRECTION UPSTREAM OF TDA					
	22894	23689	23981	24264	24997
TDA MAY-AUG FORECAST, kaf	74769	77821	79941	80280	77058
ADJUSTED TDA MAY-AUG FORECAST, kaf	51875	54133	55960	56015	52061
INITIAL CONTROLLED FLOW (ICF), kcfs (2)	326.6	343.5	356.4	356.8	328.0

Notes:

- 1 Forecasts for months other than the current month may be different than the official forecast released earlier. Differences are due to updated streamflow, precipitation, or snow data.
- 2 *Columbia River Treaty Flood Control Operating Plan*, Corps of Engineers, Northwestern Division, 2003

Questions? Contact Ken Soderlind, 503-808-3950; John McCoskery, 503-808-3951, or Patti Low, 503-808-3958.